

16

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer

DTS COPY

NAME OF WORK: Providing & Asphaltting to Pot holes filling & Road cuttings in Dasarahalli ward No 14

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	358.19		
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	298.49		
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3. back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications - Filling pot holes and patch repairs with bituminous concrete, 40mm. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	1194.00		
4	Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 4 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	358.19		

Signature of the Contractor

Number of Corrections: *Nel*

[Signature]
Executive Engineer,
Dasarahalli Division,

DTS Approved

[Signature]
Chief Engineer
Bruhat Bangalore Mahanagara Palike
Dasarahalli Zone, Bangalore